

Bidder: _____

RESURFACING BID FORM: Spring 2018 Group 3 – Old Floydburg Rd

Oldham County Fiscal Court
Attn: Melissa Horn, County Treasurer
100 West Jefferson Street, Suite 4
La Grange, Kentucky 40031

Contractor: _____

Address: _____

City, State, Zip: _____

Phone Number: _____

Total Not to Exceed Bid Price: \$ _____

| | | |
|-----------|-------|------|
| Signature | Title | Date |
|-----------|-------|------|

Requirements for bidding (These requirements become part of the contract for the successful bidder):

Project Scope:

- By making a bid, the applicant stipulates that they have visited the site and have an understanding of the scope of work and have field verified the scope.
- All gravel driveways shall be tapered in with asphalt as needed for a smooth vertical transition. All concrete and asphalt drive ways shall be keyed in for a smooth transition. Every effort has been made to identify the locations to be keyed, however it is the responsibility of the bidder to verify these locations.
- All water valves, gas valves, manholes, etc. shall be raised to the level of the new pavement. Every effort has been made to identify these locations, however it is the responsibility of the bidder to verify these items.
- In general, roads may be closed to through traffic from 9 am to 3 pm with the exception of Oldham County School buses. Exceptions may be made for the deeper culvert replacements.
- Oldham County reserves the right to make adjustments in the field. Examples include, but are not limited to, avoiding high rock, adding culvert(s), changing the size of culvert(s) and widening or deepening dig-outs. Change orders must be used and approved in advance by the County Engineer if any price difference is incurred.
- All asphalt loads must be weighted on Kentucky Transportation Cabinet Department of Highways certified scales.
- All successful bidders must adhere to the most current editions of the Kentucky Transportation Cabinet, Department of Highways Standard Specifications for Road and Bridge Construction when performing the work.

Bidder: _____

- All paving (overlay) shall include courses required to crown the centerline of the road for positive drainage. Minimum crown shall be 1/8 of an inch per foot. All overlays must be at least 1.5" thick.
- All new pavements must be to the Oldham County Road Specifications of 1" surface over 4" binder and 9" Densely Graded Aggregate (DGA).
- Any questions or differences of opinion relative to quantities or aspects of work shall be brought to the attention of the County Engineer prior to the deadline for bid submission.
- All bidders must carry a warranty for work performed in this bid package for one calendar year from the last day of performing said work.
- The start date for the project must be approved by the County Engineer. All work must be completed and invoiced by **June 23, 2018**.
- Should the price of asphalt increase more than 5 percent between the bid due date and the work completion date (per the KYTC Method Average Asphalt Price Index (AAPI)), the successful bidder may adjust the invoice with the amount greater than the 5 percent fluctuation. For purposes of an adjustment calculation, the liquid asphalt content is assumed to be 5.3 percent and the bid quantities shall be used.

Administrative Procedures:

- To be considered for this project, the Office of the County Treasurer must receive a complete bid package using this form by **Friday, March 16, 2018, 12:00 pm**.
- Bids must be submitted in a sealed envelope with the company name, street address, bid due date and project name: "**Spring 2018 Group 3 – Old Floydburg Rd**" clearly marked. Bids must be mailed or delivered to Melissa Horn, County Treasurer at the above address. Bids sent via email will not be accepted.
- All bidders and their employees, assigns, subcontractors, etc. must be fully covered by Workers Compensation. A certificate of liability insurance with workers compensation coverage must be included in the bid package.
- All bids must be signed.
- Successful bidders must be in good standing with the Kentucky Secretary of State, the Kentucky Revenue Cabinet, and must not be debarred or excluded from Federal work. IRS Form W-9 must be included with bid.
- Bids will be opened on Tuesday, **March 20, 2018** during the scheduled public Fiscal Court Meeting.
- Bid proposal shall remain unaltered unless bidders is directed otherwise by amendment.
- It is the bidder's responsibility to receive and respond to any and all amendments.
- All items/components of the project must be included in the bid.

Oldham County Fiscal Court reserves the right to waive any irregularities and/or reject any or all bids based on predetermined criteria of past performance, cost, comprehensiveness of bid proposal, etc.

Bidder: _____

Road: Old Floydsburg Rd

Length: 2700.00 **Average Width:** 18 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 445.50 tons **Unit Price:** _____ **Total:** _____

Remove and Replace Asphalt Base and Surface Courses only:

| | | | | | | |
|---------|-------|----|----|----|--------|--------------|
| Station | 5+00 | 11 | by | 11 | equals | 13.44 sq. yd |
| Station | 10+00 | 6 | by | 75 | equals | 50.00 sq. yd |
| Station | 15+00 | 6 | by | 75 | equals | 50.00 sq. yd |
| Station | 25+00 | 6 | by | 75 | equals | 50.00 sq. yd |

Quantity: 163.44 sq. yd **Unit Price:** _____ **Total:** _____

Dig Out – Full Depth:

| | | | | | | |
|---------|-------|---|----|----|--------|--------------|
| Station | 17+40 | 6 | by | 40 | equals | 26.67 sq. yd |
| Station | 18+00 | 6 | by | 25 | equals | 16.67 sq. yd |

Quantity: 43.33 sq. yd **Unit Price:** _____ **Total:** _____

Keyway:

Ash Ave Old Forest Bartlett Reamers

Quantity: 4 **Unit Price:** _____ **Total:** _____

Other Items:

| | | | | | |
|---------|-------|-------------------------------|---------|-------|-----------------|
| Station | 0+00 | Water Valve | Station | 10+20 | 2 x Water Valve |
| Station | 6+00 | Water Valve | Station | 20+00 | 7 x Water Valve |
| Station | 16+00 | Water Valve | | | |
| Station | 26+00 | 3 x Water Valve, 1x Gas Valve | | | |

Quantity: 16 **Unit Price:** _____ **Total:** _____

Station 0+00 Remove and Replace Shoulder 58' long by 4' wide, cut ditch to flow
Unit Price: _____ **Total:** _____

Station 20+00 Mill curb 400' long by 2' wide to match overlay
Unit Price: _____ **Total:** _____

Bidder: _____

Road: Old Forest Rd - Pewee

Length: 2243.00 **Average Width:** 18 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 370.10 tons Unit Price: _____ Total: _____

Wedge: 74.02 tons Unit Price: _____ Total: _____

Mill:

2243 by 18 equals 4486.00 sq. yd

Quantity: 4486 Unit Price: _____ Total: _____

Keyway:

Ash Ave
6 driveways

Quantity: 7 Unit Price: _____ Total: _____

Bidder: _____

Road: Powhatan Ln - Pewee

Length: 400.00 **Average Width:** 18 **Pavement Depth with Tack Coat:** 1.5 Inches
CuldeSac 78 by 60 ellipse 3676 sqft

Overlay: 99.70 tons Unit Price: _____ Total: _____

Wedge: 19.94 tons Unit Price: _____ Total: _____

Mill:

400 by 18 equals 800.00 sq. yd
78 by 60 ellipse 408.44 sqyd

Quantity: 1208 Unit Price: _____ Total: _____

Keyway:

5 driveways

Quantity: 5 Unit Price: _____ Total: _____

Bidder: _____

Road: Wooldridge Ave - End at the Rail Crossing - Pewee

Length: 2855.00 **Average Width:** 16 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 418.73 tons Unit Price: _____ Total: _____

Wedge: 83.75 tons Unit Price: _____ Total: _____

Mill:

2855 by 16 equals 5075.56 sq. yd

Quantity: 5076 Unit Price: _____ Total: _____

Keyway:

W Hwy 22 Wooldridge Place Peace Ln Wooldridge Ave at the Rail Crossing
17 driveways

Quantity: 21 Unit Price: _____ Total: _____

Other Items:

Remove and Replace Speed Hump x2
12' by 16' by 8"

Quantity: 2 Unit Price: _____ Total: _____

Pewee Roads Subtotal: _____

Bidder: _____

Road: Meadow Bluff Drive - Crestwood

Length: 545.00 **Average Width:** 22 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 109.91 tons Unit Price: _____ Total: _____

Wedge: 21.98 tons Unit Price: _____ Total: _____

Dig Out – Full Depth:

At Dead End 10 by 20 equals 22.22 sq. yd

Quantity: 22.22 sq. yd Unit Price: _____ Total: _____

Keyway:

Driveways 7.00

Quantity: 7 Unit Price: _____ Total: _____

Other Items:

Raise Manhole 4

Quantity: 4 Unit Price: _____ Total: _____

Bidder: _____

Road: Meadow Stream Court - Crestwood

Length: 800.00 **Average Width:** 22 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 161.33 tons Unit Price: _____ Total: _____

Wedge: 32.27 tons Unit Price: _____ Total: _____

Keyway:

Driveways 10.00

Quantity: 10 Unit Price: _____ Total: _____

Other Items:

Raise Manhole 5

Quantity: 5 Unit Price: _____ Total: _____

Bidder: _____

Road: Meadow Stream Way - Crestwood

Length: 3515.00 **Average Width:** 22 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 708.86 tons Unit Price: _____ Total: _____

Wedge: 141.77 tons Unit Price: _____ Total: _____

Keyway:

Driveways 43.00

Quantity: 43 Unit Price: _____ Total: _____

Other Items:

Raise Manhole 11

Quantity: 11 Unit Price: _____ Total: _____

Bidder: _____

Road: Falls Court - Crestwood

Length: 221.00 **Average Width:** 20 **Pavement Depth with Tack Coat:** 1.5 Inches
Cul de Sac 60 ft dia 2827 sqft

Overlay: 66.43 tons **Unit Price:** _____ **Total:** _____

Wedge: 13.29 tons **Unit Price:** _____ **Total:** _____

Keyway:

Driveways 3.00

Quantity: 3 **Unit Price:** _____ **Total:** _____

Bidder: _____

Road: Spring Hill Court - Crestwood

Length: 850.00 **Average Width:** 21 **Pavement Depth with Tack Coat:** 1.5 Inches
Cul de Sac 65 ft dia 3318 sqft

Overlay: 194.04 tons **Unit Price:** _____ **Total:** _____

Wedge: 38.81 tons **Unit Price:** _____ **Total:** _____

Keyway:

Driveways 8.00

Quantity: 8 **Unit Price:** _____ **Total:** _____

Other Items:

Raise Manhole 1

Quantity: 1 **Unit Price:** _____ **Total:** _____

Bidder: _____

Road: Spring Bluff Drive - Crestwood

Length: 1025.00 **Average Width:** 22 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 206.71 tons Unit Price: _____ Total: _____

Wedge: 41.34 tons Unit Price: _____ Total: _____

Keyway:

Driveways 10.00 At Star Barn Lane

Quantity: 11 Unit Price: _____ Total: _____

Other Items:

Raise Manhole 1

Quantity: 1 Unit Price: _____ Total: _____

Bidder: _____

Road: Spring Hill Trace - Crestwood

Length: 2400.00 **Average Width:** 24 **Pavement Depth with Tack Coat:** 1.5 Inches

Overlay: 528.00 tons Unit Price: _____ Total: _____

Wedge: 105.60 tons Unit Price: _____ Total: _____

Keyway:

Driveways 11.00 At Highway 329 At Bridge

Quantity: 13 Unit Price: _____ Total: _____

Other Items:

Raise Manhole 6

Quantity: 6 Unit Price: _____ Total: _____

Crestwood Roads Subtotal: _____