

Bidder: \_\_\_\_\_

## Request for Bids – Oldham County Fiscal Court

100 W. Jefferson Street  
LaGrange, Kentucky 40031  
502 222-1476

### Culvert Replacement for Little Huckleberry Creek under Settlers Point Trail

Contractor: \_\_\_\_\_

Address: \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

Phone Number: \_\_\_\_\_

**Total Not to Exceed Bid Price: \$ \_\_\_\_\_**

---

(Signature) / Title / Date

Oldham County Fiscal Court is accepting bids to remove existing double - 36" diameter RCP culverts and replace them with a box culvert at 13110 Settlers Point Trail. The new culvert will have an opening of 8 feet wide by 6 feet high and will be 60 feet long with wing walls.

Specific plan and profile drawings with existing utilities shown can be picked up at the Oldham County Engineer's Office for this project. All necessary permits have been obtained and are in place. All bids must include:

- Excavation and removal of the existing culverts, headwalls, and roadway necessary to construct/install new box culvert with wing walls according to the plans furnished by Oldham County;
- Controlling the flow of Little Huckleberry Creek with pump around as required by the flow and the control of all sediment on the project;
- Adjustment of the utilities as necessary, to be included;
- Backfill of the culvert and a 6" concrete cap within 1.5" of the final pavement elevation.
- All successful bidders must adhere to the most current editions of the Kentucky Transportation Cabinet, Department of Highways Standard Specifications for

Bidder: \_\_\_\_\_

Road and Bridge Construction when performing the work. Questions should be addressed to Scott Harris, Oldham County Engineer at 222-1476.

Bid shall have a lump sum price that is used to determine the lowest bidder that is the result of the combining of the following individual items that include all the work to be completed that is used to determine the level of responsibility of the bidder:

- Excavation/Removal \_\_\_\_\_
- Pump around \_\_\_\_\_
- Class A Concrete \_\_\_\_\_
- Steel \_\_\_\_\_
- Backfill/concrete cap \_\_\_\_\_
- Detour Signage \_\_\_\_\_

Administrative Procedures

To be considered for this project, the Office of the County Treasurer must receive a complete bid package using this format by **Monday, February 5, 2018, 12:00 pm.**

Bids must be submitted in a sealed envelope with the company name, street address, bid due date and project name: "Settler's Point Trail Culvert" clearly marked. Bids must be mailed or delivered to Melissa Horn, Oldham County Treasurer at the above address. Bids sent via email will not be accepted.

All bidders and their employees, assigns, subcontractors, etc. must be fully covered by Workers Compensation. A certificate of liability insurance with workers compensation coverage must be included in the bid package.

All bids must be signed.

Successful bidders must be in good standing with the Kentucky Secretary of State, the Kentucky Revenue Cabinet, and must not be debarred or excluded from Federal work. IRS Form W-9 must be included with bid.

Bids will be opened on **Tuesday, February 6, 2018** during the scheduled public Fiscal Court Meeting.

Bid proposal shall remain unaltered unless bidder is directed otherwise by amendment. It is the bidder's responsibility to receive and respond to any and all amendments.

All items/components of the project must be included in the bid.

Oldham County Fiscal Court reserves the right to award the bid when opened or at a later date and the right to waive any irregularities and/or reject any or all bids.

Oldham County [OC] will provide and/or assist with the following:

Bidder: \_\_\_\_\_

- OC will provide the Road Closed Ahead Signage and Type 3 Barricades.
- OC will remove all trees necessary for the project construction.
- Contractor will remove Subdivision Entrance Sign. Reusable materials such as the Entrance Sign itself and the stackable stones shall be placed off to the side of the project. The Subdivision Entrance Sign will not be replaced and/or reconstructed.
- OC will haul away any/all excess spoils material.
- OC will supply and deliver clean #57 and/or #2 stone for backfill as needed.
- Contractor will place and compact backfill material.
- Contractor shall provide a 6" concrete cap over the stone backfill area.
- OC will provide a 1.5" surface asphalt cap over the concrete cap area.
- OC will supply and deliver any topsoil needed for finish grade work.
- Contractor shall conduct the necessary work to complete the finish grade work.
- OC will stabilize the finish grade soils [i.e. seed, straw, matting etc.] upon completion.